



**Interior and Exterior Button Up Services
Additional Services Provided By EcoCraft Homes**

- Provide and Install Sill Plates and Mod Straps
- Provide Lally Columns (X5)
- Check Foundations for square and level
- Install Exterior Sheathing, Membrane, and Foam at Marriage wall and seams, install flexible sealant at joints
- Stack and Organize Materials
- Provide and Install Temporary Building Access entry ramp or stairs
- Install ship loose windows in gable end panels
- Confirm Floor level and Fasten Lally Column Supports to Floors
- Install Temporary Floor Treads
- Secure and Seal Marriage Wall opening
- Cut out temporary wall Framing at Marriage Walls
- Cut out temporary framing between 1st and 2nd, and 2nd and 3rd floor
- Temporary Floor Framing at Vaulted Areas to remain for working platform
- Connect Amp Connects and Test Electrical
- Confirm Chase pipes locations for home run electrical and communication
- Review All Plumbing and Mechanical stubs for field connections
- Check all Interior finishes for damage or issues

402 Highland Dr. Shippenville, PA 16254

Phone: 1-800-274-6198

Fax: 1-800-274-6198